Exova 2395 Speakman Dr. Mississauga Ontario Canada L5K 1B3

T: +1 (905) 822-4111 F: +1 (905) 823-1446 E: sales@exova.com W: www.exova.com

Testing. Advising. Assuring.



PERFORMANCE EVALUATION OF FIXED WINDOW "875 Series" For Windspec Inc.

IN ACCORDANCE WITH: AAMA/WDMA/CSA 101/I.S.2/A440-11 AND A440S1-17

Report to: Windspec Inc.

> 1310 Creditstone Road Concord, ON, Canada

L4K 5T7

Attention: Mr. Oren Anava

Telephone: 905-738-8311 Fax: 905-738-6188

Email: oren@windspec.com

Report No.: 17-06-M0115-2N

5 Pages, 1 Appendix

Proposal No.: 17-006-498606

Date: June 20, 2017

Windspec Inc. Product Manufacturer: Product Type: Fixed Window

Product Series/Model: 875 Series

Class AW - PG3360 - Size tested 1500 x 2500 mm - Fixed window Primary Product Designator:

Class AW - PG70 - Size tested 59.06 in x 98.43 in - FW

Secondary Product Designator:

Positive Design Pressure: 3360 Pa (70.18 psf) Negative Design Pressure: 3360 Pa (70.18 psf) Water Penetration Resistance: 720 Pa (15.04 psf) Air Infiltration/Exfiltration: Canadian Fixed Level Test Completion Date: June 1, 2017

Report Number: 17-06-M0115-2N



1.0 INTRODUCTION

At the request of Windspec Inc., Exova was retained to evaluate the physical performance of a Fixed Window identified as "875 Series", in accordance with AAMA/WDMA/CSA 101/I.S.2/A440-11 Standard, "NAFS — North American Fenestration Standard/Specification for windows, doors, and skylights" and A440S1-17 Canadian Supplement, as outlined in proposal number 17-006-498606.

Exova Specimen No.: 17-06-M0115-2 Type: Fixed Window Model: 875 Series

Overall Window Size: 1500 mm x 2500 mm (59.06" x 98.43")

Sampling: N/A

2.0 SAMPLE DESCRIPTION

The following sample description has verified by Exova. Details and drawings of the described test specimen, as provided by the manufacturer, have been included in Appendix A.

Product Type: Fixed Window

Frame: Fixed Window, Extruded Aluminum, 1500 mm x 2500 mm x 133.35

mm (59.06" x 59.06" x 5.25")

Joinery:

Frame: Butte Joined, fastened with five #10x2" pan head screw, joints sealed

with flexible sealant

Installation:

Test buck: Wood Buck

Fasteners: Frame perimeter fastened with ten #10x1" flat head screws, five

screws per jamb, at 450 mm (17.72") c/c

Sealant: Interior and exterior frame perimeter sealed with flexible sealant

Glazing Type: Dual glazed, tempered, overall thickness 25.4 mm (1.00"), glass

thickness 6 mm (0.24"), gas cavity size 13 mm (0.51"), stainless steel

spacer, dual sealed, air filled

Glazing Method: Laid in glazed, wet glazed

Glazing Stop Extruded Aluminum interior perimeter

Glazing Spline: EPDM, one row, interior perimeter, at glazing stop, corners sealed

with flexible sealant

Setting block: Rubber, 14, 65 mm x 25 mm x 6 mm (2.56" x 0.98" x 0.24"), four per

jamb, 550 mm (21.65") c/c, three per head/sill, 610 mm (24.02") c/c Plastic, three, 120 mm x 30 mm x 5 mm (4.72" x 1.18" x 0.20"), sill,

under rubber setting blocks

Glazing Tape: Butyl, one row, exterior perimeter

Needle Bead: Flexible sealant, exterior surface at upstanding leg

Reinforcement: None

Thermal Break: Glass reinforced nylon, two rows, 18 mm (0.71"), frame perimeter



3.0 TEST RESULTS

Table 1 - Summarized Testing Results in Accordance with AAMA/WDMA/CSA 101/I.S.2/A440-11 and A440S1-17 Canadian Supplement

	A440	S1-17 Canadian	Supplement			
Test	Requireme	ents	Res	Rating		
Initial Air Leakage Resistance (Clause 9.3.2) Per ASTM E283 Test Date:	Allowable rate of air le less than or equal to L/s.m² (cfm/ft²), at the s pressure Test Pressure, Pa (psf): Gateway:	the following, subsequent test :: 300 (6.27) 1.5 (0.30)	Test area, m² (f Measured Air L L/s.m² (c) Infiltration:	PASS Canadian Fixed Level		
May 18, 2017 Initial Water Penetration	Canadian Fixed Level: No water leakage shall the following specified differential, Pa	cyclic pressure a (psf):	Exfiltration: 0.06 (0.01) No water leakage was observed at the following specified cyclic pressure differential, Pa (psf):		PASS	
Resistance (Clause 9.3.3)	Gateway Performance: Gateway Performance:				Gateway (AW40-FW)	
Per ASTM E547 Test Date: May 18, 2017	Test Pressure: Optional Perfo (US / CAI		Test Pressure: 390 (8.15) Optional Performance: (US / CAN)		Optional Performance	
	Test Pressure (US):	580 (12.11)	Test Pressure:	720 (15.04)	(AW100-FW)	
	Test Pressure (CAN):	720 (15.04)				
Initial Water	No water leakage shall the following specified differential, Pa	static pressure	No water leakage was observed at the following specified static pressure differential, Pa (psf):		PASS	
Penetration Resistance	Gateway Perfor	rmance:	Gateway Performance:		Gateway	
(Clause 9.3.3) <i>Per</i>	Test Pressure:	390 (8.15)	Test Pressure:	390 (8.15)	(AW40-FW)	
ASTM E331 Test Date: May 18, 2017 Life Cycle Testing: (Clause 7.3.5) Per AAMA 910-10 Test Date: May 29, 2017	Optional Perfo (US / CAI		Optional Performance: (US / CAN)		Optional Performance	
	Test Pressure (US):	580 (12.11)	Test Pressure:	720 (15.04)	(AW100-FW)	
	Test Pressure (CAN):	720 (15.04)				
	No damage to fastend parts, supports arm mechanisms or any of which causes the malfunction after six following temperature: Low Temperature:	ers, hardware s, actuating other damage window to cycles of the	No damage to fasteners, hardware parts, supports arms, window fully functional		PASS	

Table 1, Continued - Summarized Testing Results in Accordance with AAMA/WDMA/CSA 101/I.S.2/A440-11 and A440S1-17 Canadian Supplement

A44051-17 Canadian Supplement								
Test	Requireme		Res	Rating				
Uniform Load Deflection	No member shall defl L/175 of unsupported following specified test (psf):	span at the	Measured net deflection of Left Jamb, mm (in):		PASS			
(Clause 9.3.4.2)	Allowable deflection 14.29 (0.5		Left Jamb span, mm (in): 2500 (98.43)		Gateway (AW40-FW)			
Per ASTM E330	Gateway Perfor	mance:	Positive:	0.08 (0.003)	Optional Performance			
Test Date: June 1, 2017	Test Pressure:	±1920 (40.10)	Negative:	-1.13 (-0.04)				
	Optional Perfor	mance:			(AW70-FW)			
	Test Pressure:	±3360 (70.18)						
Post Design	Allowable rate of air lea		Test area, m² (ft²): 3.75 (40.37)					
Pressure Air Leakage Resistance (Clause 9.3.2) Per	less than or equal to the L/s.m² (cfm/ft²), at the supressure	ubsequent test	Measured Air Leakage Rate, L/s.m² (cfm/ft²):		PASS Canadian			
ASTM E283	Test Pressure, Pa (psf):	300 (6.27)						
Test Date:	Gateway:	1.5 (0.30)	Infiltration:	0.06 (0.01)				
June 1, 2017	Canadian Fixed Level:	0.2 (0.04)	Exfiltration:	0.06 (0.01)				
Post Design Pressure	No water leakage shall the following specified differential, Pa	cyclic pressure	No water leakage was observed at the following specified cyclic pressure differential, Pa (psf):		PASS			
Water Penetration	Gateway Perfor	mance:	Gateway Pe	Gateway				
(Clause 9.3.3)	Test Pressure:	390 (8.15)	Test Pressure:	390 (8.15)	(AW40-FW)			
Per ASTM E547	Optional Performance: (US / CAN)		Optional Performance: (US / CAN)		Optional Performance			
Test Date:	Test Pressure (US):	580 (12.11)	Test Pressure:	720 (15.04)	(AW100-FW)			
June 1, 2017	Test Pressure (CAN):	720 (15.04)						
Post Design Pressure Water Penetration (Clause 9.3.3) Per ASTM E331 Test Date: June 1, 2017	No water leakage shall the following specified differential, Pa	static pressure	No water leakage was observed at the following specified pressure differential, Pa (psf):		PASS			
	Gateway Perfor	mance:	Gateway Performance:		Gateway			
	Test Pressure:	390 (8.15)	Test Pressure:	390 (8.15)	(AW40-FW)			
	Optional Perfor (US / CAN		Optional Performance: (US / CAN)		Optional Performance			
	Test Pressure (US):	580 (12.11)	Test Pressure:	720 (15.04)	(AW100-FW)			
	Test Pressure (CAN):	720 (15.04)						

Table 1, Continued - Summarized Testing Results in Accordance with AAMA/WDMA/CSA 101/I.S.2/A440-11 and A440S1-17 Canadian Supplement

••										
Test	Requirements					Results		Rating		
Uniform Load Structural (Clause 5.3.4.3)	There shall be no permanent damage to the window components after the following specified test pressures, Pa (psf). No member shall have permanent deflect more that 0.2% of span.				he Pa nt	Measured permanent deflection of Left Jamb, mm (in):		PASS Gateway (AW40-FW) Optional Performance (AW70-FW)		
Per ASTM E330	Allowable permanent deflection, mm (in): 5.33 (0.21)				nm	Left Jamb span, mm (in): 2500 (98.43)				
	Gateway Performance:			Positive:	0.42 (0.02)					
Test Date: June 1, 2017	Test pressur	re:	±28	380 (60.	.15)	Negative:	0.05 (0.002)	(AW70-FW)		
	Optional Performance:									
	Test pressure: ±5040 (105.26)				5.26)					
Forced-Entry Resistance	No entry shall be gained during the following test sequence:			For Type D Windo						
(Clause 9.3.5)	Load	de Loa	Loads, N (lbf)		gained during the to specified test sequ	PASS				
Per ASTM F588	Identification	10	20	30	40			Grade 40		
Took Date:	Disassembly T1:	5 min		10 min		Disassembly T1:	No Entry			
Test Date: June 1. 2017	Manipulation T1:	5	5 min		nin	Manipulation T1:	No Entry			



4.0 MODIFICATIONS

No modification was made to the Windspec Inc., Fixed Window "875 Series," Exova Specimen No.: 17-06-M0115-2, during testing to achieve the results stated in this report.

5.0 CONCLUSIONS

Based on the results of the testing summarised in Table 1, Windspec Inc., Fixed Window "875 Series," Exova Specimen No.: 17-06-M0115-2 met the following requirements as outlined in the AAMA/WDMA/CSA 101/I.S.2/A440-11 standard and A440S1-17 Canadian Supplement.

Performance Rating

Air Leakage Resistance
 Water Penetration Resistance
 Uniform Load Deflection
 Uniform Load Structural
 Pass (Fixed Level Canadian)
 580 Pa (12.11 psf) (US)
 720 Pa (15.04 psf) (CAN)
 ±3360 Pa (70.18 psf)
 ±5040 Pa (105.26 psf)

Forced Entry Resistance Grade 40

Product Designation for Class AW:

- Class AW PG3360 Size tested 1500 x 2500 mm Fixed Window
- Class AW PG70 Size tested 59.06 x 98.43 in FW

Product Manufacturer: Windspec Inc.

Product Type: Fixed Product Series/Model: 875 Series

Primary Product Designator: Class AW – PG3360 – Size tested 1500 x 1800 mm – Fixed window

Class AW - PG70 - Size tested 59.06 x 98.43 in - FW

Secondary Product Designator:

Positive Design Pressure: 3360 Pa (70.18 psf)
Negative Design Pressure: 3360 Pa (70.8 psf)
Water Penetration Resistance: 720 Pa (15.04 psf)
Air Infiltration/Exfiltration: Canadian Fixed Level

Test Completion Date: June 1, 2017
Report Number: 17-06-M0115-2N

6.0 REPORT REVISION SUMMARY

Revision No:Date:Description of Revisions:Original2017-June-20Original Document

Reported by: Reviewed by:

Scott Hallam, Ext. 11511

Building System Specialist, Building Systems

Products Testing Division

Haya Soghrati, B.Arch. Sc, (Building Science), Ext. 11227 Fenestration Services Project Manager, Building Systems Product Testing Division

APPENDIX A

Manufacturer's Detail Drawings (2 Pages)



